

PROJECT DOCUMENTATION

Outline

- **Review Lecture 11**
- **What is a project document?**
- **Why and When is a project document required? Is necessary?**
- **Steps in developing a project document**
- **Documentation of Construction Progress**
- **Documentation of Safety Hazards & Violations**
- **Minutes of Meetings**
- **Construction Photographs**

What is a Project document?

There are two key words:

- Project
- Document

A *project* refers to a specific undertaking or venture that is to be carried out within an identified *time frame*.

A *document* is a record of information relating to a particular subject or matter.

***A project document* is a record of information about a venture or undertaking. This type of document:**

- Is descriptive (background, and type of project)**
- Outlines the process of implementation**
- Is analytical (context and conditions influencing the project and tracking mechanisms)**
- Identifies risks, challenges and benefits)**
- Identifies cost and possible sources of funding.**

Why A Project Document Is Required

- ❑ As proof of understanding about what is to be done**
- ❑ Evidence of commitment to undertake the venture in view of risks and challenges.**
- ❑ Appreciation of the cost dimensions and acceptance to work within the agreed costs**
- ❑ Measuring tool**

When is a project document required?

- When a project is conceived/create**
- As an attachment to support proposal for financial assistance**
- As evidence that a project is feasible**

Is Document necessary?

Yes!

As a reference point regarding the project

Provides information about the project

Serves as reference for preparing other project documents

Steps in preparing a project document

A project document must include the following headings:

1. Project Objective

- ✓ Project development objective (*what the project seeks to do*);
- ✓ Key performance indicators (*sets out the indicators to be used to measure and monitor the project outputs and long term outcomes*)

2. Project description

- ✓ **project components and sub-components**
- ✓ **Key policy and institutional reforms supported by the project**
- ✓ **Financial management arrangements**

3. Project rationale

- ✓ **Significance of the project**
- ✓ **Relate the significance to other projects that have been conducted**
- ✓ **Lessons learn and how these are reflected in the project design**

4. Cost

The funds required .

5. Sustainability and risks

- ✓ **Sustainability: indicate the long term sustainability of the project.**
- ✓ **Risk: identify the critical risks (i.e. these reflect the failures of the critical assumptions related to the project)**

6. Monitoring, reviewing and Reporting

7. Annexes: any document that is relevant to the project to which reference is made in the document.

Documentation of Construction Progress

- Daily Report
- Weekly Report
- Monthly Report
- Variation Order

Documentation of Safety Hazards & Violations

SITE SAFETY PLAN JOB HAZARD ANALYSIS - EXAMPLE

JHA Rev.# 0		Job or Operation Title: Example	
Location Sikorsky Aircraft Corporation		Job Address 6900 Main Street, Stratford, CT	Employees /Subs Example
Date JHA Performed Example		Team Performing JHA Example	Verified By Example
Special or Primary Hazards		Confined space, electrical shock, dust generation, power tools	
Scope of Work		Install a flow monitoring device in manhole by Col. K20.	
Personal Protective Equipment		Retrieval equipment and 4-gas meter, steel-toed boots, safety glasses, nitrile gloves, work gloves, Hard Hat, Tyvek Suit.	
Basic Job Steps		Existing and/or Potential Hazards	Corrective Measures/Controls
Loading & unloading equipment		Slip, trip, and fall, injury during lifting	Use appropriate lifting technique Wear steel-toed boots
Traffic control (vehicular & pedestrian)		- Collisions with equipment, fall/trips into trenches & manholes, close equipment-human working area	- Set up cones and caution tape around manhole area prior to opening manhole; - Be aware of equipment operating range within indoor (confined) work spaces.
Mobilize materials & equipment / Rigging Treatment System Equipment		- Material handling & equipment movement	- Rig with positive connections & provide spotter - Stay clear of lifted loads
Enter Confined Space		- Asphyxiant and combustible gases - Slips, Trips, Falls	- Use of confined space entry permit. - Use tether for confined space entrants - Monitor air quality with 4-gas meter - Always have a supervisor and attendant present and attentive during confined spaces.
Electrical Equipment and Tools		- Serious injury from drill - Electrical shock	- Wear work gloves and steel toed boots when operating drill. - Keep all body parts away from drill during operation. - Use ground fault circuit interrupter on electrical cords including extension cords.
Dust Generation		- Dust in breathing zone during drilling	- Use a vacuum equipped with a HEPA filter during drilling to prevent airborne particulates.

'First Day' Health, Safety and Security Induction Form

(This is not an exhaustive document. Inductions must address issues which are specific to each department and each position.)

Inductee's Name:	Position:
Department:	Manager's Name:
Site:	Date:

The BBC is committed to providing a healthy, safe and secure environment in which to create and broadcast great programmes and content. This document outlines key points to ensure that new employees can keep themselves and others healthy, safe and secure while working for the BBC.

Please complete the following checklist making sure you have understood all information and taken action where necessary. Your Line Manager will be able to give you advice, particularly regarding the provisions and procedures in your work environment.

Furthermore, the [Health & Safety Essentials](#) section on [myRisks Information](#) should also be read.

Key:



Important information



Manager is required to provide advice regarding local arrangements



Action is required by the inductee (e.g. mandatory training)

Responsibilities for Managing Occupational Risk	Understood / Actioned?	
	Yes	No
 Employer's Responsibilities: The Director General is ultimately accountable for all aspects of safety at the BBC. Responsibility for safety is then cascaded down the management structure. All managers are responsible for ensuring that safe systems of work are established, maintained and implemented by all staff in their area.	▼	▼
 BBC Safety BBC Safety provide specialist advice and support across the BBC and monitors compliance with Health, Safety, Fire, Security and standards. Further information can be found on myRisks . (NB: links need to be double-clicked and require macros to be enabled.)	▼	▼
 Safety Advice Line Should you need advice on any aspect of managing health, safety, security or fire related risks in your work for the BBC, contact the Safety Advice Line: Tel: 08704110464 (extension 0464) Email: ask.ak@bbc.co.uk	▼	▼
 Occupational Health Occupational Health offers advice to all staff regarding work-related health issues and travel: Occupational Health Information The BBC has a confidential counselling service to support individuals and managers: Information about confidential counselling for individuals and managers Tel: 0800 269616	▼	▼
If work is causing or affecting ill-health, you need to inform your manager and seek advice from or be referred to Occupational Health. Managers can refer staff to Occupational Health by calling: Tel: 0800 082 8080	▼	▼
 Health & Safety Co-ordinators Some areas of the BBC have Health & Safety Co-ordinators who are responsible for co-ordinating and monitoring Health & Safety arrangements within their team. You need to be made aware who the Health & Safety Co-ordinator is in your area.	▼	▼

Job Safety Analysis

Number:		Activity/ task name:		Location:	
Developed by:				Date:	
Approved by:				Date:	
Consulted with:				Date for review:	
Description of Activity/ Work Task			Statutory & Non Statutory		
Describe what this JSEA covers, the purpose of the task etc:			List all relevant regulations, standards and guidance notes		
SAMPLE					
Who is at risk? [Tick relevant answers]					
<input type="checkbox"/> Staff		<input type="checkbox"/>		<input type="checkbox"/> Other	
Potential Environmental Hazards					
<input type="checkbox"/> Air pollution (dust & fumes)	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/> Work at heights	<input type="checkbox"/> Manual Handling	
<input type="checkbox"/> Noise Pollution	<input type="checkbox"/>	<input type="checkbox"/> Confined Space	<input type="checkbox"/> Light/ dark	<input type="checkbox"/> Hot/ Cold	
<input type="checkbox"/> Spills to water	<input type="checkbox"/>	<input type="checkbox"/> Ignition sources	<input type="checkbox"/> Chemical	<input type="checkbox"/> Pressure/ Stored Energy	
<input type="checkbox"/> Other:	<input type="checkbox"/>	<input type="checkbox"/> Other:	<input type="checkbox"/>	<input type="checkbox"/> Other:	
Hazardous Chemicals [List any hazardous chemicals to be used - Attach MSDS/SDS]			Fire/ Emergency Equipment Requirements [e.g. fire extinguisher, rescue gear etc]		
1.	2.	1.			
3.	4.	2.			

MoM



TeamworX

MINUTES OF MEETING	MoM No. : QR-CM-1931-P-004-MOM-001
	Date : 29 July 2009
	Project No. : 1931
Project Title : Fresh Milk Project - Nestle Kejayan Factory	
Place : Engineering Meeting Room - Nestle Kejayan Factory	
Time : 11.00 – 13.00	
Subject : Kick Off Meeting	
Attendances :	
Nestle Kejayan Factory (Owner)	1. Arjo H.T 2. Anto Basuki 3. Andita K.D 4. Sonni P
TeamworX (CM Consultant)	1. Ferdinand F 2. Erwin P.S
First Choice International (Contractor)	1. Teguh S 2. Candra Gunawan 3. Askur 4. Djumaryono 5. Sunhajj

Rev.	Date	Description	Prepared	Checked
0	29/07/2009	For Information	FF	AAB

QF-CM-004, Rev.00	Document By : TeamworX	Doc. Date : 01-Jan-09
-------------------	---------------------------	--------------------------

Construction Photographs



TeamworX
Construction Management Services
1931-Nestlé Kejayan Factory-Fresh Milk Unloading Station Project



Morning safety talk



Base course material



Compacted gravel



Compacted gravel



CBR test



CBR test

Construction Photographs



TeamworX

Construction Management Services

1931-Nestlé Kejayan Factory-Fresh Milk Unloading Station Project



Drainage work



Pouring concrete for pipe rack column



Unloading steel material



Column erection C1



Column erection P2 C1



Column erection P1 & P2

Thank You for your attention